

Report #PR Municipal Pool and Therapy Pool

| <i>Item/Location</i> | <i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i> | <i>Action</i> | <i>Priority</i> | <i>Target Date</i> | <i>Estimated Cost</i> | <i>Interim Solution</i> | <i>Action Completion Date</i> |
|--|--|---|-----------------|--------------------|---------------------------|-------------------------|---------------------------------------|
| 01-Site Entrance Signage: North Entrance to the Parking Lot. | Warning signage contains appropriate wording and information. | Apply required phone number to sign in minimum 1" high numbers. Fill in the phone number of the local law enforcement agency at the bottom of the sign. | 1 | 2009 - 2010 | \$53.60 | | |
| 02-Parking, General: Public Parking Area. | | | 1 | 2009 - 2010 | \$0.00 | | |
| 03-Double Parking Space: At the West Side of the Therapy Pool. [One double handicap parking space design including one Van Accessible handicap parking space.] | 2% max. surface slope in any direction within parking space & access aisle. "NO PARKING" letters are a minimum of 12" high and visible to traffic enforcement officials. | Remove asphalt to comply with 2% maximum cross slope. Minor asphalt overlay (1" avg. or less). Install striping and surface identification for double accessible parking stall. | 1 | 2009 - 2010 | \$6,080.84 | | |
| 04-Walks and Sidewalks: At the West Side of the Therapy Pool. [From the double handicap parking space design in Item #3 to the West entrances into the Therapy Pool and Municipal Pool.] | 2% max. cross slope. | Replace existing sidewalk toward the Western entrance at the Municipal Pool. | 1 | 2009 - 2010 | \$3,981.33 | | |
| 05-Double Parking Space: North Side of the Municipal Pool. [One double handicap parking space design to be removed.] | Parking space has 18' minimum length. Parking space has minimum 18' x 5' wide access aisle between stalls (8' min. if one is Van Accessible). 2% max. surface slope in any direction within parking space & access aisle. Wheel stops at each space, if necessary, to prevent vehicle(s) from encroaching into required clear width of sidewalk. HC parking sign with symbol of accessibility is installed at each space. The words "NO PARKING" are painted in white on the ground within each access aisle. "NO PARKING" letters are a minimum of 12" high and visible to traffic enforcement officials. | Blackout existing handicap parking space. Remove sign. | 1 | 2009 - 2010 | \$290.94 | | |

Report #PR Municipal Pool and Therapy Pool

| <i>Item/Location</i> | <i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i> | <i>Action</i> | <i>Priority</i> | <i>Target Date</i> | <i>Estimated Cost</i> | <i>Interim Solution</i> | <i>Action Completion Date</i> |
|--|---|---|-----------------|--------------------|---------------------------|-------------------------|---------------------------------------|
| 06-Doors: West Entrance to the Municipal Pool. [One set of double doors (one operational).] | The international symbol of accessibility is posted at all primary entrances. | Post a sign/decal displaying the "International Symbol of Accessibility" at the primary entrance. | 2 | 2009 - 2010 | \$15.32 | | |
| 07-Clear Space at Doors: West Entrance to the Municipal Pool. [One set of double doors (one operational).] | Floor or landing is level and clear (2% max. slope). | Install level exterior door landing. | 2 | 2009 - 2010 | \$2,296.93 | | |
| 08-Sales and Service Counters: Interior Transaction Counter at the Municipal Pool. | A portion of the counter is a minimum of 36" in length, at a height between 28" - 34" above the floor and; | Provide an auxiliary counter with a maximum height of 34". | 2 | 2009 - 2010 | \$995.34 | | |
| 09-Doors: West Entrance to Therapy Pool. [One single door.] | Bottom 10" of door has a smooth uninterrupted surface. The international symbol of accessibility is posted at all primary entrances. | Remove door stop. Post a sign/decal displaying the "International Symbol of Accessibility" at the primary entrance. | 2 | 2009 - 2010 | \$53.60 | | |
| 10-Clear Space at Doors: West Entrance to Therapy Pool. [One single door.] | | | 2 | 2009 - 2010 | \$0.00 | | |
| 11-Walks and Sidewalks: Deck at Interior of Therapy Pool. | 2% max. cross slope. | Replace existing deck. | 2 | 2009 - 2010 | \$2,296.93 | | |
| 12-Water Fountains (Drinking): By the Women's Restroom at the Interior of the Therapy Pool. | 32" min. wide and 18" min. deep alcove provided. Bubbler outlet is 36" max. from floor. Two fountains are provided, one that is wheelchair accessible and one at normal height for those persons having difficulty bending or stooping. | Lower existing drinking fountain. Install cane-detectable barrier around fountain. Install paper cup dispenser at existing fountain. | 2 | 2009 - 2010 | \$1,385.82 | | |
| 13-Doors: Leading Out to Municipal Pool. | Bottom 10" of door has a smooth uninterrupted surface. | Remove door stop. | 2 | 2009 - 2010 | \$38.28 | | |
| 14-Clear Space at Doors: Leading Out to Municipal Pool. | Floor or landing is level and clear (2% max. slope). Minimum strike side clearance on PULL side of door: 24" exterior doors. Minimum strike side clearance on PUSH side of door: 12" front approach with latch and closer. | Install level exterior door landing. Remove restricting objects. Move boxes, carts, non-fixed trash receptacles, etc. to provide required minimum door swing and clear space. | 2 | 2009 - 2010 | \$3,521.96 | | |

Report #PR Municipal Pool and Therapy Pool

| <i>Item/Location</i> | <i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i> | <i>Action</i> | <i>Priority</i> | <i>Target Date</i> | <i>Estimated Cost</i> | <i>Interim Solution</i> | <i>Action Completion Date</i> |
|--|--|--|-----------------|--------------------|---------------------------|-------------------------|---------------------------------------|
| 15-Walks and Sidewalks: Deck at Municipal Pool. | 5% max. surface slope in direction of travel. 2% max. cross slope. | Replace existing sidewalk at the entrances to both restrooms. Correct deficiencies at both entrances to the restrooms. | 1 | 2009 - 2010 | \$6,125.13 | | |
| 16-Telephones: At Municipal Pool. [One bank of one telephone.] | Volume controls are provided on one phone in each bank and on 25% of all other public phones. Telephones with volume controls are hearing aid compatible (blue grommet) and shall have hearing aid compatible signage. | Install signage for volume control or text telephone or contact the phone company to make the modification. Replace telephone with one that has volume control or contact the phone company to make the modification. Install cane detectable barriers at both sides of the phone. | 4 | 2009 - 2010 | \$1,462.37 | | |
| 17-Water Fountains (Drinking): At Municipal Pool. | 32" min. wide and 18" min. deep alcove provided. | Install cane-detectable barriers around fountain. | 2 | 2009 - 2010 | \$735.02 | | |
| 18-Controls, Operating Mechanisms & Vending Machines.: Pepsi, Aquafina, and Gatorade Machines at the Municipal Pool. | Highest operable part of the object is a maximum of 54" above the floor surface. | Contact the provider to install a compliant Gatorade machine. | 3 | 2009 - 2010 | \$0.00 | | |
| 19-Doors: Women's Restroom. [No door.] | | | 2 | 2009 - 2010 | \$0.00 | | |
| 20-Identification Symbols, Restrooms: Women's Restroom. | Signs are centered on door 60" from floor. Wall mounted signage: 6" min. symbol of accessibility is mounted on wall adjacent to latch side of door. | Install wall-mounted sign at single entrance. Relocate existing signage. | 3 | 2009 - 2010 | \$267.97 | | |
| 21-Multiple Accommodation Toilets: Women's Restroom. | Door has loop or U-shaped handle immediately below latch on both inside and outside of door. 17" - 19" to top of seat. Front of toilet paper dispenser is within 36" of the back wall. | Install additional interior stall door hardware. Provide a toilet seat to comply with the maximum height requirement of 17" - 19". Relocate the toilet paper dispenser away from the top of the grab bars. | 2 | 2009 - 2010 | \$423.95 | | |
| 22-Toilet Grab Bars: Women's Restroom. [See Item #21 for recommendations.] | Center of bar is 33" to 36" above floor. Area directly above grab bars or proposed grab bars is free of protruding obstructions to a height of 18" (recessed items are allowed). | | 3 | 2009 - 2010 | \$0.00 | | |
| 23-Lavatories: Women's Restroom. | | | 3 | 2009 - 2010 | \$0.00 | | |

Report #PR Municipal Pool and Therapy Pool

| <i>Item/Location</i> | <i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i> | <i>Action</i> | <i>Priority</i> | <i>Target Date</i> | <i>Estimated Cost</i> | <i>Interim Solution</i> | <i>Action Completion Date</i> |
|---|--|---|-----------------|--------------------|---------------------------|-------------------------|---------------------------------------|
| 24-Accessories: Women's Restroom. | 48" max. height to coat hooks. Accessories do not require tight grasping, pinching or twisting of the wrist to operate. | Install accessible coat hook. Replace existing timer with standard light switch. | 3 | 2009 - 2010 | \$306.26 | | |
| 25-Showers - (roll in compartment): Women's Restroom. | Wide portion of seat extends max. of 15" from adjacent wall. | Relocate existing seat. | 3 | 2009 - 2010 | \$76.57 | | |
| 26-Showers - Part 2: Women's Restroom. | Continuous grab bar is provided along the walls opposite from and adjacent to the seat. 60" min. hose on shower spray head. Fixed head located 48" above floor. Shower spray unit and hose is located a max. of 24" from the back of the wall on which the seat is mounted. Soap dish is mounted on the control wall at 40" max. height. | Install compliant grab bars. Relocate soap dish. Provide shower spray unit and hose. | 3 | 2009 - 2010 | \$1,094.39 | | |
| 27-Electrical Controls & Receptacles/Fire Alarm Boxes: Women's Restroom. | | | 3 | 2009 - 2010 | \$0.00 | | |
| 28-Doors: Men's Restroom. [No door.] | | | 2 | 2009 - 2010 | \$0.00 | | |
| 29-Identification Symbols, Restrooms: Men's Restroom. | Wall mounted signage: 6" min. symbol of accessibility is mounted on wall adjacent to latch side of door. | Install wall-mounted sign at single entrance. | 3 | 2009 - 2010 | \$114.85 | | |
| 30-Multiple Accommodation Toilets: Men's Restroom. [Drain just outside accessible stall.] | Door has loop or U-shaped handle immediately below latch on both inside and outside of door. Front of toilet paper dispenser is within 36" of the back wall. | Install additional interior stall door hardware. Relocate the toilet paper dispenser away from the top of the grab bar. Replace existing sidewalk at drain. | 2 | 2009 - 2010 | \$1,071.90 | | |
| 31-Toilet Grab Bars: Men's Restroom. [See Item #30 for recommendations.] | Area directly above grab bars or proposed grab bars is free of protruding obstructions to a height of 18" (recessed items are allowed). | | 3 | 2009 - 2010 | \$0.00 | | |
| 32-Lavatories: Men's Restroom. | 34" max. height to rim or counter. | Lower existing lavatory. | 3 | 2009 - 2010 | \$1,378.15 | | |
| 33-Urinals: Men's Restroom. | | | 3 | 2009 - 2010 | \$0.00 | | |
| 34-Accessories: Men's Restroom. | 48" max. height to coat hooks. Accessories do not require tight grasping, pinching or twisting of the wrist to operate. | Install accessible coat hook. Replace existing timer with standard light switch. | 3 | 2009 - 2010 | \$306.26 | | |
| 35-Showers - (roll in compartment): Men's Restroom. | Wide portion of seat extends max. of 15" from adjacent wall. | Relocate existing seat. | 3 | 2009 - 2010 | \$76.57 | | |

Report #PR Municipal Pool and Therapy Pool

| <i>Item/Location</i> | <i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i> | <i>Action</i> | <i>Priority</i> | <i>Target Date</i> | <i>Estimated Cost</i> | <i>Interim Solution</i> | <i>Action Completion Date</i> |
|--|---|--|-----------------|--------------------|---------------------------|-------------------------|---------------------------------------|
| 36-Showers - Part 2: Men's Restroom. | Continuous grab bar is provided along the walls opposite from and adjacent to the seat. 60" min. hose on shower spray head. Fixed head located 48" above floor. Shower spray unit and hose is located a max. of 24" from the back of the wall on which the seat is mounted. | Install compliant grab bars. Install soap dish at compliant height. Provide shower spray unit and hose. | 3 | 2009 - 2010 | \$1,094.39 | | |
| 37-Electrical Controls & Receptacles/Fire Alarm Boxes: Men's Restroom. | The center of electrical receptacles or controls, and switches to control lighting, heating, cooling & appliances are 48" max. above the floor or working platform. | Relocate electrical switch. | 3 | 2009 - 2010 | \$1,131.38 | | |
| 38-Doors: East Entrance to the Pool Office. [See Item #39 for recommendations.] | 1/4" max. vertical threshold or 1/2" beveled at 1:2. | | 2 | 2009 - 2010 | \$0.00 | | |
| 39-Clear Space at Doors: East Entrance to the Pool Office. | Floor or landing is level and clear (2% max. slope). Minimum strike side clearance on PUSH side of door: 12" front approach with latch and closer. | Install level exterior door landing. Move non-fixed trash receptacles to provide required minimum door clear space. | 2 | 2009 - 2010 | \$3,062.56 | | |
| 40-Doors: North Entrance to the Municipal Pool. [One gate.] | Door hardware is operable with a single effort (lever type, panic bar or push pull type). Bottom 10" of door has a smooth uninterrupted surface. The international symbol of accessibility is posted at all primary entrances. | Replace door hardware with compliant hardware. Install kick-plate to bottom of door. Post a sign/decal displaying the "International Symbol of Accessibility" at the primary entrance. | 2 | 2009 - 2010 | \$375.16 | | |
| 41-Clear Space at Doors: North Entrance to the Municipal Pool. | Floor or landing is level and clear (2% max. slope). | Install level exterior door landing. | 2 | 2011 - 2012 | \$2,296.93 | | |
| 42-Walks and Sidewalks: At the North Side of the Municipal Pool. [From the gate in Item #40 West.] | | | 2 | 2011 - 2012 | \$0.00 | | |
| Report Year 2009 - 2010 Total | | | | | \$42,410.70 | | |
| Entire Report Total | | | | | \$42,410.70 | | |