

<i>Item/Location</i>	<i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i>	<i>Action</i>	<i>Priority</i>	<i>Target Date</i>	<i>Estimated Cost</i>	<i>Interim Solution</i>	<i>Action Completion Date</i>
01-Site Entrance Signage: West Entrance into the Parking Lot. [Provide a site entrance sign into the parking lot. Fill in the phone number of the local law enforcement agency at the bottom of the sign.]	Warning signage is posted conspicuously at each entrance to off-street parking facilities or adjacent to parking stall(s).	Install pole-mounted signage. Apply required phone number to sign in minimum 1" high numbers.	1	2015 - 2016	\$321.57		
02-Parking, General: Throughout the Parking Lot. [No delineated on-site parking.]			1	2015 - 2016	\$0.00		
03-Walks and Sidewalks: Between the Museum and School House. [Provide an accessible path of travel.]	Continuous common surface is not interrupted by steps or abrupt changes in level (less than 1/4" vertical or 1/2" beveled at 1:2).	Install new sidewalk.	1	2015 - 2016	\$5,379.41		
04-Van Accessible Parking Space: At the South Side of the School House. [One proposed Van Accessible handicap parking space.]	Parking space has 18' minimum length.	Minor asphalt overlay (1" avg. or less). Install striping and surface identification for Van Accessible stall. Install post-mounted Van-Accessible signage at stall.	1	2015 - 2016	\$3,599.34		
05-Walks and Sidewalks: At the South Side of the School House. [From the proposed Van Accessible handicap parking space in Item #4 to the pedestrian ramp at the East side of the School House. See Items #3 and #4 for additional memos and the recommendations.]	Continuous common surface is not interrupted by steps or abrupt changes in level (less than 1/4" vertical or 1/2" beveled at 1:2).		2	2015 - 2016	\$0.00		

<i>Item/Location</i>	<i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i>	<i>Action</i>	<i>Priority</i>	<i>Target Date</i>	<i>Estimated Cost</i>	<i>Interim Solution</i>	<i>Action Completion Date</i>
06-Pedestrian Ramps: At the East Side of the School House. [One 39"+ or - pedestrian ramp. See Item #7 for additional memo and recommendations.]	Ramps do not exceed allowable lengths. (40' up to 6.25%, 37.5' up to 6.67%, 30' up to 8.33%). 8.33% max. surface slope. 48" minimum width. 60" x 60" min. top landing. 72" minimum bottom landing. 2% max. slope of bottom landing. Handrails are provided on both sides. 60" minimum length of intermediate landings. 2% maximum in any direction.	Replace pedestrian ramp. Replace top landing for ramp. Install bottom landing for ramp. Install intermediate landing for ramp.	2	2015 - 2016	\$7,579.85		
07-Ramp Handrails: At the East Side of the School House. [One 39"+ or - pedestrian ramp.]	Handrails are on both sides and continuous. 1-1/4" to 1-1/2" grip portion diameter or cross section equivalent. 34" - 38" finish height above ramp surface to top of rail. 12" min. level extension beyond top and bottom of ramp.	Install wall-mounted handrails. Replace free-standing handrails.	2	2015 - 2016	\$9,532.52		
08-Doors: East Entrance to the School House.	1/4" max. vertical threshold or 1/2" beveled at 1:2. Bottom 10" of door has a smooth uninterrupted surface. The international symbol of accessibility is posted at all primary entrances.	Replace the threshold. Install kick-plate to bottom of door. Post a sign/decal displaying the "International Symbol of Accessibility" at the primary entrance.	2	2015 - 2016	\$229.69		
09-Clear Space at Doors: East Entrance to the School House. [See Item #6 for recommendations.]	60" min. clear space in direction of door swing.		2	2015 - 2016	\$0.00		
10-Aisles: Interior of the School House.			2	2015 - 2016	\$0.00		
11-Walks and Sidewalks: Between the School House and Pump Museum. [Provide a compliant path of travel.]	Continuous common surface is not interrupted by steps or abrupt changes in level (less than 1/4" vertical or 1/2" beveled at 1:2).	Install new sidewalk.	1	2015 - 2016	\$2,366.94		
12-Single Parking Space: At the South Side of the Pump Museum. [One single handicap parking space.]	Parking space has 18' minimum length. Parking space has minimum 18' x 5' wide access aisle provided on the passenger side. 2% max. surface slope in any direction within parking space & access aisle. The words "NO PARKING" are painted in white on the ground within each access aisle. "NO PARKING" letters are a minimum of 12" high and visible to traffic enforcement officials.	Remove and replace existing concrete parking stall and access aisle with compliant parking stall and access aisle not to exceed 2% maximum cross slope in any direction. Install striping and surface identification.	1	2015 - 2016	\$6,416.07		

Report #PR School House and Pump Musuem

<i>Item/Location</i>	<i>Barrier (noted feature, item or area does not meet the new construction criteria detailed below)</i>	<i>Action</i>	<i>Priority</i>	<i>Target Date</i>	<i>Estimated Cost</i>	<i>Interim Solution</i>	<i>Action Completion Date</i>
13-Signage: At the South Side of the Pump Museum. [Post the International Symbol of Accessibility at the head of the single handicap parking space in Item #12 with an arrow pointing North for access to the Pump Museum.]	Directional and Informational Signage: Letters and numbers on signs have a 3:5 to 1:1 width to height ratio.	Install pole-mounted directional signage.	2	2015 - 2016	\$267.97		
14-Walks and Sidewalks: At the South Side of the Pump Museum. [From the single handicap parking space in Item #12 to the South entrance into the Museum.]	Continuous common surface is not interrupted by steps or abrupt changes in level (less than 1/4" vertical or 1/2" beveled at 1:2). 2% max. cross slope.	Replace existing sidewalk at change of direction. Grind elevated edges of existing sidewalk outside the Southern entrance.	1	2014 - 2015	\$535.95		
15-Doors: South Entrance to the Pump Museum.	Door hardware is operable with a single effort (lever type, panic bar or push pull type). The international symbol of accessibility is posted at all primary entrances.	Replace door hardware with compliant hardware. Post a sign/decal displaying the "International Symbol of Accessibility" at the primary entrance.	2	2014 - 2015	\$313.92		
16-Clear Space at Doors: South Entrance to the Pump Museum.			2	2014 - 2015	\$0.00		
17-Aisles: Interior of the Pump Museum.			2	2014 - 2015	\$0.00		
Report Year 2015 - 2016 Total					\$36,543.23		
Entire Report Total					\$36,543.23		